Contact: Allison Loat, Production Coordinator (204) 786-9970

a.loat@uwinnipeg.ca

ASPER CENTRE FOR THEATRE AND FILM Technical Specifications (subject to change) – Main Theatre, 1T15

Summary of Staffing Rates and Conditions can be found on page 3 or by clicking on the following link: http://theatre.uwinnipeg.ca/download/trentconditions.pdf

Loading Dock

- Located on Balmoral Street (One-way) 8' x 10' overhead loading door at dock level direct to the stage. Call for information about full tractor trailer length and access schedule. 36" W X 48" dock plate available (750lb capacity)

Parking

-No parking provided by venue

Seating Capacities

Stock End Stage Configuration*

- Main floor raked seating bank: 107
- Balcony seating accessed by separate entrance (NOT wheelchair accessible): 48
- Total Stock capacity: 155
- Maximum Occupancy load: **300**
- *Please consult venue on seating capacity for any non traditional configurations. Reconfigurations are available for an additional cost.

Stage Specs & Related Equipment

Stage Dimensions

- Flexible black box space with maximum dimensions of: 64' x 42'9"
- Stock end stage configuration: 27'(w) x 25'(d)
- Stage depth from down stage edge to back wall: 36'5 1/2"
- Centre line to stage left: 21'4 1/2"
- Centre line to stage right: 21'4 1/2"
- Stage left wing space: 2'9"
- Stage right wing space: 3'11" (Maximum vertical clearance of wing 8'6")

Stock Masking

- Three legs per side, opening at: 13'6" (From centre line)
- Upstage traveller (control on stage right) at: 25'(From downstage edge)

Grid & Hang Positions

- High steel: 25'2"
- Lighting head rail: 24'0"
- Lighting mid rail (not recommended for lighting fixtures): 21'0"
- Lighting knee rail (suggested hanging position for lighting fixtures): 20'6"
- Lighting toe rail (ladder access only): 17'6"
- Clearance under catwalks: 17'4"
- Clearance under SR gallery: 8'8"

Stage Floor

- Sprung floor Masonite top, matte black finish
- Additional fee for restoring floor if painted or altered by way of screws, scratches, other "non wear and tear" use

Contact: Allison Loat, Production Coordinator (204) 786-9970

a.loat@uwinnipeg.ca

ASPER CENTRE FOR THEATRE AND FILM Technical Specifications (subject to change) – Main Theatre, 1T15

Control Booth

- Accessed via balcony entrance (NOT wheelchair accessible)
- Dedicated positions for lighting technician, stage manager, sound mixer

Stage Draperies (listed as height x width)

Stock Plot Drapes – included as hung in stock configuration

- 17'3" x 4'0": DSR Leg	- 8'9" x 5'0": DSR Leg under gallery
- 7'9" x 5'0": DSR Leg above gallery	- 17'3" x 12'0" (5): Stock Legs with return
- 17'3" x 22'0" (2): US Traveller	- 3'0" x 36'0": Border for Traveler track

Additional Masking (subject to availability)

-17'3" x 12'0": (3)	-17'3" x 20'0": (2)	-17'3" x 4'0":	(2)
-8'10" x 10'0": (1)	-7'9" x 5'0": (2)	-7'0" x 4'0":	(3)
-6'0" x 44'0": (3)	-3'0" x 36'0": (1)		

Backstage Spaces

Green Room (450 ft²)

- Full sized refrigerator and kettle - Program sound - 1 accessible washroom - Direct path to stage

- Dressing rooms directly off of green room

Dressing Room A

- Capacity of 10 (254 ft²) - Program sound - Separate accessible washroom - Accessible shower facilities

Dressing Room B

- Program sound - Capacity of 6 (169 ft²) - Separate accessible washroom - Accessible shower facilities

Production Office

- Wi-Fi available

Lighting

Dimming

- 2 ETC Sensor+ dimmer racks, 192 @ 20A dimmers. 4 used for house lights

Lighting Console

- ETC Ion 1024 output, software version 2.7.3 as of Feb. 6th 2019
- ETC 2x20 fader wing
- ETC remote video interface available upon advanced request only

Network

- Please consult Technical Director if planning to integrate with existing network
- ETC DMX/RDM Gateways located throughout catwalks
- -Touring gateway available for ground package *upon advanced request only*

Contact: Allison Loat, Production Coordinator (204) 786-9970

a.loat@uwinnipeg.ca

ASPER CENTRE FOR THEATRE AND FILM Technical Specifications (subject to change) – Main Theatre, 1T15

House Lighting Plot

- -Link to PDF and paperwork
- House Plot
- Magic Sheet

Lighting Notes (For additional lighting beyond the stock plot):

- Re-hanging lights is at additional cost to be negotiated prior to the scheduled booking.
- Due to other ongoing studio activities, the available inventory is flexible and details will be provided once scheduling has been completed.
- Restoration of the basic configuration must be included in the labour charges at the users' expense and must take place within the scheduled booking.
- Colour filters, gobos and lighting accessories may be made available at additional cost.

Audio

Loudspeakers

- Main left and right: 2 x JBL AC2212/64 per side
- Subwoofer: 1 JBL ASB6118 mounted permanently upstage centre
- Monitors: 1 JBL AC2212/64 upstage left and right respectively *Reconfigurable for an additional fee
- Spares: 2 x JBL AC2212/64 *Available by prior arrangement for and additional fee

Console

- Mackie PRO FX16
- Roland M400 V Mixer *Regiures second technician

Stock Audio Equipment

- iMac running Qlab 4 for playback
- 2 x Denon DN615 CD players
- 2 x Active DI boxes (Mono)
- 1 x Passive DI box (Stereo)
- 4 x SM 58 Microphone
- 2 x AKG Wireless hand held condenser microphone

Additional Audio Equipment *Requires second technician to operate

- 16 x 8 Digital audio snake
- 4 x AKG WMS 450 beltpacks
- 6 x AKG CK99 Lapel mics
- 2 x Countryman E6 ear sets
- 6 x Countryman B6 Lav clip on mics

Projection *Available for an additional cost

Control Locations

- Stock control location in booth (Blue Ray, HDMI and VGA connections available)
- Auxiliary control location from on stage portable podium Plug in on stage right. (HDMI, VGA, Blue Ray Player and Composite Video connections available)

Contact: Allison Loat, Production Coordinator (204) 786-9970 a.loat@uwinnipeg.ca

ASPER CENTRE FOR THEATRE AND FILM Technical Specifications (subject to change) – Main Theatre, 1T15

Main Projector

- Epson Z8050 7000 Lumen WXGA with standard zoom lens (1.71-2.78 ratio) Fixed in place.
- 198" Draper 16:10 motorized screen (in center of room, see space drawing). Fixed in place.

Auxiliary Projection

- 2 x Epson PowerLite 1835 XGA 3500 lumen standard zoom (1.8-2.24)
- 3 x Epson PowerLite 430 XGA 3000 lumen Wide Throw (0.54-0.71) fixed lens
- 4 x City Theatrical Projector dowsers (controlled by DMX via lighting board)
- 4 VGA connection locations in main lighting grid via CAT 5 Extender (1 house left and 1 house right Catwalk 3; 1 at center Catwalk 4; and 1 at center Catwalk 5)
- 1 4x4 VGA matrix switcher in booth (connected to main VGA drop locations)

Supervision and Labour

This is a summary of key points only and is subject to change. For complex or custom setups, estimates are available in advance.

- The basic rental includes one technician for up to 8 working hours per day. This technician will be available as an operator for rehearsals and performance. No activities of any kind may occur in the theatre without the supervision of a technician.
- This technician must be provided with a one-hour meal break after 5 consecutive hours of work AND the first call of the day may not be less than 3 hours
- Supplementary technical crews can be made available at additional cost.
- A house manager and ushers can be made available at additional cost.
- Public events require lobby supervision throughout the duration of the event.

Regular Rates (subject to change):

- Primary Theatre Technician: Included in daily rental rate for 8 working hours
- Additional Theatre Technician: \$15.00 / hour
- Technical Crews or Ushers: \$13.50 / hour
- House Manager: \$15.00 / hour

Overtime (subject to change):

Overtime charges are DOUBLE THE REGULAR RATE and are pro-rated to the nearest half hour or part and apply to ALL positions.

- Daily work hours exceeding 5 hours without a 1-hour meal break (no activity permitted in the theatre at meal breaks)
- Daily, regular work hours exceeding 8 hours (excluding meal breaks)
- Weekly, regular work hours exceeding 40 hours
- Any work on a 7th consecutive day (in lieu of a day off) See contract for more information
- Any work between 1:00am and 7:00am
- Any work on a Statutory Holiday

Overtime Rates

- Primary Theatre Technician: \$30.00 / hour
- Additional Technician: \$30.00 / hour
- Technical Crew(s) / Usher(s): \$27.00 / hour
- House Manager: \$30.00 / hour